

BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE
Office Of The Executive Engineer, Dasarahalli Project Division
SCHEDULE-B

NAME OF THE WORK: Improvement works at Dog Kennel Sy No 51 Mallasandra war no 13 of Project subdivision

SI No	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications. Asper the Directon Of Enggineer -in-charge of the work	Cum	196.00	169.56	Rupees One hundred and Sixty nine and Fifty six paise Only
2	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications Asper the Directon Of Enggineer -in-charge of the work	Cum	225.69	288.12	Rupees Two hundred eighty eight and Twelve Paise only
3	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead upto 50m. and lift of 1.5m, complete as per specifications Asper the Directon Of Enggineer -in-charge of the work	Cum	61.06	2283.12	Rupees Two Thousand Hundred Eighty three and Twelve Paise only
4	KSRB 4-1.2 : Providing and laying in position plain cement concrete of cum mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Asper the Directon Of Enggineer -in-charge of the work	Cum	58.78	5449.68	Rupees Five thousand four hundred forty nine and Sixty eight paise only
5	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. Asper the Directon Of Enggineer -in-charge of the work	Cum	195.10	4521.96	Rupees Four thousand and Five hundred twenty one and Ninty six Paise Only
6	KSRB 2.3: Filling available excavated earth (excluding rock) in sides cum of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification. Asper the Directon Of Enggineer -in-charge of the work	Cum	202.00	137.16	Rupees One hundred and Thirty seven and Sixteen Paise Only

[Signature]
EXECUTIVE ENGINEER-4
 KRIDL, BBMP Division tractor
 BENGALURU-560 010

[Signature]
Executive Engineer
Dasarahalli Project Division
 Project Division
 Bruhat Bangalore Mahanagara Palike,
 Dasarahalli Zone, Bangalore-73.

7	KSRB 4.2.8: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels, and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. As per the Director Of Engineer -in-charge of the work	Cum	76.70	6650.64	Rupees Six thousand and six hundred fifty and Sixty four Paise Only
8	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications up to 3.50m from Ground level. Specification No As per the Director Of Engineer -in-charge of the work	Sqm	280.00	338.04	Rupees Three hundred and thirty eight and Four Paise Only
9	KSRB 4-6.9 Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications. As per the Director Of Engineer -in-charge of the work	Sqm	15.20	732.24	Rupees Seven hundred Thirty two and Two four Paise Only
10	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, Sqm propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. As per the Director Of Engineer -in-charge of the work	Sqm	205.15	276.48	Rupees Two hundred seventy six and Fourty Eight Paise Only
11	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. As per the Director Of Engineer -in-charge of the work.	Tn	7.99	65455.56	Rupees Sixty Five thousand four hundred and fifty five and Fifty six Paise Only
12	KSRB 6-2.4 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0 Newton per sqmm with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. As per the Director Of Engineer -in-charge of the work	Cum	80.51	7520.04	Rupees Seven thousand five hundred and twenty and Four Paise Only
13	KSRB 6-7.2 : Construction of partition wall 11.2 cms thick with non modular ground moulded burnt bricks of class designation 5.0 Newton per sqmm with cement mortar 1:4 including providing and fixing plaster mesh manufactured out of hot dipped galvanised iron of nominal thickness 0.35 mm. 100 mm. wide as per I.S. 2212/1991 at 7.5 m. c to c including cost of materials, labour charges, scaffolding, curing complete as per specifications. As per the Director Of Engineer -in-charge of the work	Sqm	209.50	1007.64	Rupees One thousand and seven and Sixty four Paise Only

EXECUTIVE ENGINEER-4
SIGNALS & BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER
Dasarahalli Zone, Project Division
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-73.